Fjordview Kommune

Fjordview Community Centre

Tender Reference FCC-2026-T01

Document 03

Employer's Requirements

Revision	Date	Status	Prepared by	Checked by
P01	2026-10-03	Issued for Tender	Fjordview Kommune Project Team	Nordvik Rådgivning AS

This document forms part of the tender documents for the above project. It is issued for tendering purposes only and must not be used for construction.

Note: this is a synthetic example tender pack prepared for a technical interview exercise. The project, parties and figures are fictional.

1. Purpose and status

This document sets out the Employer's requirements for the design completion and construction of the Fjordview Community Centre. It describes the scope, the performance the completed building must achieve and the standards to which the Contractor shall complete the design. The Architectural and MEP Specifications (Documents 04 and 05) describe materials and workmanship in more detail; where a requirement here is more onerous than a Specification, this document prevails.

Requirements expressed with 'shall' are mandatory. Requirements expressed with 'should' are preferred and departures must be identified in the Tenderer's statement of compliance. 'May' indicates an option available to the Contractor.

2. Scope of the Works

The Works comprise: completion of the design from the tender stage; demolition of the existing depot buildings; remediation of localised hydrocarbon contamination; construction of the new building; external works including a surface car park, landscaping, service yard and cycle parking; utility connections; supply and installation of the commercial kitchen equipment; testing, commissioning and handover; and seasonal commissioning for 12 months after Completion.

Loose furniture, audio-visual equipment and public art are covered by provisional sums and are not otherwise included. ICT active equipment is excluded; structured cabling and containment are included.

3. Design responsibility matrix

The Contractor is responsible for completing the design of all elements. The matrix below indicates the stage to which the Employer's design has been developed and the consultant who will be novated.

Element	Employer design stage	Novated	Contractor completes to
Architecture	Stage 3 / MMI 350	Yes - Arkitektkontor Vest AS	MMI 500
Structure	Stage 3 / MMI 350	Yes - Nordvik Rådgivning AS	MMI 500
Civil and drainage	Stage 2 / MMI 300	Yes - Nordvik Rådgivning AS	MMI 500
Mechanical and ventilation	Stage 2 / MMI 300	No	MMI 500
Electrical and ICT	Stage 2 / MMI 300	No	MMI 500
Fire engineering	Stage 3 strategy	No	Full design
Acoustics	Performance criteria only	No	Full design
Kitchen equipment	Schedule of equipment	No	Full design
Landscape	Stage 3	Yes - Arkitektkontor Vest AS	MMI 500

4. Site and external works

4.1 Demolition and remediation

The existing depot buildings (approx. 1,100 m2) and hardstanding shall be demolished and removed. Hydrocarbon contamination has been identified around the former fuel store; the Contractor shall remove and dispose of up to 300 m3 of contaminated material within the Contract Sum. Quantities in excess of 300 m3 will be dealt with under provisional sum PS4.

4.2 Levels and drainage

Finished floor level L00 shall be set at +3.80 m above sea level (NN2000) to provide a 200-year flood margin. Surface water shall be attenuated on site to a discharge rate of 5 l/s with a 1-in-20-year storage volume and a climate factor of 1.4.

4.3 Landscape

External areas shall be designed to a biodiversity net gain of 10% using the municipal calculator. A minimum of 25 new trees of semi-mature size (16-18 cm girth) shall be planted. Hard landscaping shall use permeable paving to parking bays and local granite setts to the entrance plaza.

4.4 Car and cycle parking

The car park shall provide 48 car parking spaces, of which 4 shall be accessible spaces located within 30 m of the main entrance, and 8 shall be provided with electric vehicle charging points (22 kW). Ducting shall be provided to allow charging to be extended to a further 16 spaces in future.

Covered cycle parking for 60 bicycles shall be provided adjacent to the main entrance, with 10 additional spaces for cargo bikes. Six staff showers are included in the changing rooms.

4.5 Service yard

A service yard shall be provided to the north-east of the building serving the kitchen, with space for a 10 m rigid delivery vehicle to turn, refuse and recycling stores for 8 x 1,100 l containers, and a screened external store for the kitchen grease separator.

5. The building

5.1 General

The building shall be designed for a service life of 60 years for the structure and envelope and 25 years for building services. It shall achieve universal design in accordance with TEK17 Chapter 12 and the Employer's accessibility brief.

5.2 Structure

The structure shall be designed to Eurocodes with Norwegian national annexes. Imposed floor loads: Main Hall 5.0 kN/m2; Library 4.0 kN/m2 (stack areas 7.5 kN/m2); offices 3.0 kN/m2; plant room 7.5 kN/m2. The Main Hall roof shall be free of internal columns.

5.3 Envelope

External walls shall achieve a U-value not exceeding 0.22 W/m2K, roof 0.13 W/m2K and windows 0.80 W/m2K (whole window). Airtightness shall not exceed 0.6 air changes per hour at 50 Pa. The Contractor may propose an alternative roofing membrane to that specified in Document 04 provided it carries a 25-year manufacturer's warranty and is approved by the Employer's

Representative.

5.4 Internal planning

Room areas, adjacencies and clear heights are given in the room data sheets in Section 8. Clear heights are measured from finished floor to the underside of the lowest element (ceiling, exposed structure or services) and shall not be reduced without the Employer's written agreement.

5.5 Fire strategy

The building is risk class 5, fire class 2. The fire strategy prepared by the Employer is included for information; the Contractor shall appoint a fire engineer to complete the strategy. The Main Hall shall accommodate 600 persons with four exits. Protected escape corridors C-01 (L00) and C-02 (L01) shall be enclosed in 60-minute fire-resisting construction.

5.6 Doors to escape routes

All doors opening onto the protected escape corridors C-01 and C-02 shall be fire doors achieving 60 minutes' integrity with cold smoke seals (FD60S), fitted with closers and intumescent strips, and shall be inspected and certified by a third party before Completion. Doors on the final exit route from the Main Hall shall open outward with panic hardware.

5.7 Acoustics

See Section 6.2.

5.8 Finishes

Floor finishes shall be hard-wearing and suitable for a public building: linoleum to circulation and multi-purpose rooms, sprung timber to the Main Hall, carpet tiles to the Library and offices, and resin to the kitchen. Wall finishes shall be impact-resistant to 1.2 m in all public areas.

5.9 Vertical transportation

Two passenger lifts shall be provided, each with a minimum capacity of 13 persons (1,000 kg), serving L00 and L01 and the roof plant level, one of which shall be sized as a firefighting lift in accordance with the fire strategy. A goods lift is not required; kitchen deliveries are at L00.

6. Performance criteria

6.1 Thermal comfort and ventilation

Internal temperatures shall be maintained between 20 and 24 degrees C in all occupied spaces for 95% of occupied hours. Mechanical ventilation shall be provided to all occupied spaces at not less than 8 l/s per person, with demand control on CO2 to the Main Hall, Library and multi-purpose rooms. Specific fan power shall not exceed 1.5 kW/(m3/s).

6.2 Acoustics

Airborne sound insulation between rooms shall meet NS 8175 class B and in any case the following:

Separating construction	Minimum Rw (dB)
Music Room (L01-110) to Library (L01-104)	55

Separating construction	Minimum Rw (dB)
Music Room to practice rooms	52
Multi-purpose rooms to each other	48
Offices to corridors	40
Main Hall to foyer	52

Reverberation time in the Main Hall shall be adjustable between 1.0 and 1.6 seconds at 500 Hz. Mechanical services noise shall not exceed NR 30 in the Library and Music Room and NR 35 elsewhere.

6.3 Lighting

Illuminance: Main Hall 300 lux (dimmable), Library 500 lux at reading surfaces, offices 500 lux, kitchen 500 lux, circulation 150 lux. All lighting shall be LED with presence and daylight control. Emergency lighting to NS-EN 1838 with 3-hour duration.

6.4 Electrical

The incoming supply shall be sized for the maximum demand assessed by the Contractor with 25% spare capacity. The Contractor shall confirm the supply agreement with the network operator (BKK Nett). A standby generator is not required; the fire alarm, emergency lighting and lift shall have battery or UPS backup as required by the fire strategy.

7. Energy and sustainability

7.1 Energy performance

The building shall achieve energy label A under the Norwegian energy labelling scheme and a calculated net delivered energy not exceeding 95 kWh/m2 per year. Heating shall be by ground-source heat pump with the municipal district heating connection as back-up.

7.2 Embodied carbon

Embodied carbon (A1-A5) shall not exceed 280 kg CO2e/m2 GIFA, a reduction of 30% against the reference building. The Contractor shall provide a climate gas account (klimagassregnskap) at Completion.

7.3 On-site renewable generation

A roof-mounted photovoltaic array of not less than 50 kWp shall be provided, connected to the main switchboard with export metering agreed with BKK Nett. The roof structure and the PV support structure are included in the structural scope; the modules, inverters, cabling and connection are included in the electrical scope. The array shall be accessible for maintenance from the roof plant level.

7.4 Water

Potable water consumption shall not exceed 15 litres per person per day through low-flow fittings. Rainwater harvesting for WC flushing is optional.

8. Room data sheets

The room data sheets below summarise the key requirements for each principal space. Full room data sheets are held in the project BIM model.

L00-001 Entrance Foyer and Reception

Level	Net area (m2)	Clear height	Floor finish	Lighting
L00	180	4,200 mm	Granite setts / resin	300 lux
Fittings and notes	Reception desk, display, lockers			

L00-010 Main Hall

Level	Net area (m2)	Clear height	Floor finish	Lighting
L00	520	6.0 m (double height, to underside of glulam roof structure)	Sprung timber	300 lux dimmable
Fittings and notes	Retractable seating 300, stage 60 m2, acoustic drapes			

L00-011 Main Hall Store

Level	Net area (m2)	Clear height	Floor finish	Lighting
L00	45	3,000 mm	Resin	200 lux
Fittings and notes	Racking, double doors 1,800 mm			

L00-020 Cafe and Servery

Level	Net area (m2)	Clear height	Floor finish	Lighting
L00	140	3,200 mm	Linoleum	300 lux
Fittings and notes	Servery counter 6 m, 60 covers			

L00-021 Commercial Kitchen

Level	Net area (m2)	Clear height	Floor finish	Lighting
L00	110	3,000 mm	Resin, coved skirting	500 lux
Fittings and notes	See MEP Specification Section 7 for equipment schedule. Includes combi oven OV-01 (18 kW), walk-in freezer FZ-01, walk-in chiller CH-01			

L00-022 Kitchen Dry Store

Level	Net area (m2)	Clear height	Floor finish	Lighting
L00	25	3,000 mm	Resin	200 lux
Fittings and notes	Racking			

L00-023 Kitchen Staff Change

Level	Net area (m2)	Clear height	Floor finish	Lighting
L00	25	2,700 mm	Vinyl	200 lux
Fittings and notes	Lockers, shower			

L00-030 Multi-purpose Room 1

Level	Net area (m2)	Clear height	Floor finish	Lighting
L00	90	3,500 mm	Linoleum	300 lux
Fittings and notes	Folding partition to MPR 2			

L00-031 Multi-purpose Room 2

Level	Net area (m2)	Clear height	Floor finish	Lighting
L00	90	3,500 mm	Linoleum	300 lux
Fittings and notes	Folding partition to MPR 1			

L00-032 Multi-purpose Room 3

Level	Net area (m2)	Clear height	Floor finish	Lighting
L00	60	3,500 mm	Linoleum	300 lux
Fittings and notes	Dance mirrors one wall			

L00-040 Changing Rooms and Showers

Level	Net area (m2)	Clear height	Floor finish	Lighting
L00	150	2,700 mm	Vinyl, slip resistant	200 lux
Fittings and notes	6 showers, 40 lockers, accessible WC			

L00-050 Protected Escape Corridor C-01

Level	Net area (m2)	Clear height	Floor finish	Lighting
L00	85	2,700 mm	Linoleum	150 lux
Fittings and notes	60-minute enclosure; FD60S doors			

L01-104 Library and Reading Room

Level	Net area (m2)	Clear height	Floor finish	Lighting
L01	420	3,600 mm	Carpet tile	500 lux at desks
Fittings and notes	Shelving 1,200 linear m, 80 reading places			

L01-110 Music Room

Level	Net area (m2)	Clear height	Floor finish	Lighting
L01	100	3,600 mm	Timber	300 lux
Fittings and notes	Rw 55 dB to Library; acoustic treatment			

L01-111 Practice Room 1

Level	Net area (m2)	Clear height	Floor finish	Lighting
L01	20	3,000 mm	Carpet tile	300 lux
Fittings and notes	Rw 52 dB			

L01-112 Practice Room 2

Level	Net area (m2)	Clear height	Floor finish	Lighting
L01	20	3,000 mm	Carpet tile	300 lux
Fittings and notes	Rw 52 dB			

L01-120 Offices (open plan)

Level	Net area (m2)	Clear height	Floor finish	Lighting
L01	200	3,000 mm	Carpet tile	500 lux
Fittings and notes	24 workstations			

L01-121 Meeting Room 1

Level	Net area (m2)	Clear height	Floor finish	Lighting
L01	40	3,000 mm	Carpet tile	500 lux
Fittings and notes	12 persons, AV			

L01-122 Meeting Room 2

Level	Net area (m2)	Clear height	Floor finish	Lighting
L01	40	3,000 mm	Carpet tile	500 lux
Fittings and notes	12 persons, AV			

L01-130 Youth Club

Level	Net area (m2)	Clear height	Floor finish	Lighting
L01	190	3,600 mm	Linoleum	300 lux
Fittings and notes	Kitchenette, games area			

L01-150 Protected Escape Corridor C-02

Level	Net area (m2)	Clear height	Floor finish	Lighting
L01	70	2,700 mm	Linoleum	150 lux
Fittings and notes	60-minute enclosure; FD60S doors			

L02-201 Plant Room

Level	Net area (m2)	Clear height	Floor finish	Lighting
Level 2	110	3,500 mm	Sealed concrete	200 lux
Fittings and notes	AHUs, heat pump, switchboard; access via lift and stair			

9. Planning conditions to be discharged by the Contractor

Condition	Summary	Timing
3	Construction environmental management plan	Before commencement
5	Details of external materials and samples	Before superstructure
7	Landscape planting plan and management plan	Before Completion
9	Surface water drainage strategy	Before commencement
11	Details of PV array and roof plant screening	Before roof works
14	Travel plan including cycle parking	Before Completion

10. Submittals and review

The Contractor shall submit for review, not less than 20 working days before the relevant work commences, the following: product data sheets, samples where requested, method statements, fabrication drawings, and evidence of compliance with the standards cited in this section. Review by the Employer's Representative does not relieve the Contractor of responsibility for compliance with the Contract.

At completion the Contractor shall provide operation and maintenance manuals, as-built drawings in native and PDF format, commissioning records, warranties and training for the Employer's facilities staff.