Fjordview Kommune

Fjordview Community Centre

Tender Reference FCC-2026-T01

Document 04

Architectural Specification

Revision	Date	Status	Prepared by	Checked by
P01	2026-10-03	Issued for Tender	Fjordview Kommune Project Team	Nordvik Rådgivning AS

This document forms part of the tender documents for the above project. It is issued for tendering purposes only and must not be used for construction.

Note: this is a synthetic example tender pack prepared for a technical interview exercise. The project, parties and figures are fictional.

1. General

1.1 Scope

This Specification covers the architectural elements of the Works: roof coverings, external walls, windows and curtain walling, internal partitions, doors and ironmongery, finishes, fixed furniture and signage. It is to be read with the Employer's Requirements (Document 03) and the Drawings (Document 06). Structural and MEP elements are specified in Documents 05 and the structural information on the Drawings.

Prepared by Arkitektkontor Vest AS on behalf of the Employer. The Contractor shall complete the specification to construction level as part of its design obligations.

1.2 Standards

Materials and workmanship shall comply with the Norwegian Standards and European Standards current at the date of tender except where a specific edition is cited. Reaction-to-fire and resistance-to-fire classification of products shall be in accordance with NS-EN 13501-1:2007 and NS-EN 13501-2:2016 respectively. Where a product's declaration of performance cites a later edition, the Contractor shall demonstrate equivalence.

1.3 Submittals

The Contractor shall submit for review, not less than 20 working days before the relevant work commences, the following: product data sheets, samples where requested, method statements, fabrication drawings, and evidence of compliance with the standards cited in this section. Review by the Employer's Representative does not relieve the Contractor of responsibility for compliance with the Contract.

1.4 Quality

Work shall be executed by suitably trained and experienced operatives under competent supervision. The Contractor shall maintain an inspection and test plan for the works in this section and shall give the Employer's Representative not less than two working days' notice of hold points.

1.5 Samples and mock-ups

The Contractor shall provide a 3 m x 3 m sample panel of the rainscreen cladding including a window head, sill and jamb, and a 2 m x 2 m sample of each floor finish, for approval before procurement. Approved samples shall be retained on site as the standard for the Works.

2. Roof coverings

2.1 Main roof

The main roof shall be a warm roof comprising a single-ply polymer membrane (PVC or FPO, 1.8 mm) mechanically fixed to tapered PIR insulation on a vapour control layer on the structural deck. The membrane shall be a product from an approved manufacturer carrying a 25-year warranty, unless an alternative is approved by the Employer's Representative under Employer's Requirements Section 5.3.

The roof shall achieve a U-value not exceeding 0.13 W/m2K and shall be designed for the PV support structure described in the Employer's Requirements Section 7.3 and the roof plant loads given on the structural drawings. Walkways of paving slabs on pedestals shall be provided to all plant and to the PV array for maintenance access.

2.2 Main Hall roof

The Main Hall roof is a glulam structure exposed internally. The roof build-up above the glulam deck shall be as for the main roof with the addition of an acoustic absorbent layer between the deck and the insulation to achieve the reverberation criteria. The underside of the glulam shall be left exposed with a fire-retardant clear finish achieving class B-s1,d0.

2.3 Rooflights

Six rooflights of 1,500 x 1,500 mm shall be provided over the Library with triple glazing, U-value 1.0 W/m2K, motorised opening for smoke ventilation where required by the fire strategy.

3. External walls

3.1 Rainscreen cladding

External walls shall be a ventilated rainscreen of vertical larch boarding (heartwood, untreated) on battens, on a breather membrane, on a timber frame with 250 mm mineral wool insulation, with an internal vapour control layer and plasterboard lining. The complete wall shall achieve a U-value not exceeding 0.22 W/m2K.

Cladding within 1.2 m of ground level and to the service yard elevation shall be fibre cement panels (A2-s1,d0) in place of timber. Timber cladding shall not be used on the north elevation within 5 m of the school boundary; use fibre cement panels.

3.2 Windows and curtain walling

Windows shall be aluminium-clad timber, triple glazed, whole-window U-value not exceeding 0.80 W/m2K, g-value 0.35 to south and west elevations and 0.50 elsewhere. The foyer and cafe elevations shall be thermally broken aluminium curtain walling with the same glazing performance. All opening lights shall be restricted to 100 mm except where designated for smoke ventilation.

3.3 Airtightness

The envelope shall be tested to NS-EN ISO 9972 and shall not exceed 0.6 air changes per hour at 50 Pa. Two tests are required: one at completion of the envelope and one at Completion.

4. Internal partitions

4.1 Partition types

Partition types are scheduled below. Acoustic performance is the laboratory Rw of the partition; the Contractor shall select constructions and detail junctions so that the site performance meets the Employer's Requirements Section 6.2.

Type	Location	Construction	Fire resistance	Acoustic Rw (dB)
PT-01	General partitions, offices, meeting rooms	92 mm metal stud, 2 x 12.5 mm plasterboard each side, 50 mm mineral wool	EI 30	44
PT-02	Corridor walls to protected escape corridors C-01 and C-02	146 mm metal stud, 2 x 15 mm fire-rated plasterboard each side, 100 mm mineral wool	EI 60	48
PT-03	Between multi-purpose rooms (fixed sections)	146 mm metal stud, 2 x 12.5 mm plasterboard each side, 100 mm mineral wool	EI 30	50
PT-04	Music Room (L01-110) to Library (L01-104)	Twin frame 2 x 92 mm metal stud independent, 2 x 15 mm plasterboard each side, 2 x 50 mm mineral wool	EI 60	-
PT-05	Practice rooms	Twin frame as PT-04 with resilient bars	EI 30	52
PT-06	Main Hall to foyer	200 mm blockwork, plastered, plus independent lining one side	EI 60	55
PT-07	Kitchen and food stores	146 mm metal stud, moisture resistant board, hygienic cladding	EI 60	44
PT-08	Plant room enclosure	200 mm blockwork, fair faced	EI 60	50
PT-09	WC cubicles	Solid grade laminate system	-	-
PT-10	Folding partition MPR 1 / MPR 2	Proprietary acoustic folding wall	-	48

4.2 Workmanship

Partitions shall be taken to the underside of the structural soffit and fire-stopped. Deflection heads shall be provided under all floor and roof structures. Service penetrations shall be fire-stopped with tested systems and recorded in the fire-stopping register.

5. Doors and ironmongery

5.1 General

Internal doors shall be solid core flush doors with hardwood lippings and veneered faces. Veneers should preferably be from certified Nordic species; the Tenderer may propose alternatives in its statement of compliance. The reference veneer for pricing is beech. All doors shall achieve the fire and smoke performance stated in the schedule and shall be supplied as certified doorsets with frames, seals and ironmongery from a single source.

Fire doors shall be third-party certified and labelled. Doors with the suffix S shall have cold smoke seals. Vision panels in fire doors shall be fire-rated glass of the same rating as the door.

5.2 Door schedule

Widths are structural opening widths in mm. Heights are leaf heights in mm.

Door	Location	Room	Width	Height	Type	Fire / smoke	Ironmongery / notes
D-G01	Main entrance (external)	L00-001	1,800 (2 No. 900 leaves)	2,400	Aluminium, glazed, automatic sliding	-	Access control, automatic

Door	Location	Room	Width	Height	Type	Fire / smoke	Ironmongery / notes
D-G02	Entrance lobby (internal)	L00-001	1,800 (2 No. 900 leaves)	2,400	Aluminium, glazed, automatic sliding	-	Automatic
D-G03	Reception office	L00-001	1,000	2,100	Timber, veneered	FD30S	Lock, closer
D-G04	Main Hall from foyer (pair)	L00-010	1,800 (2 No. 900 leaves)	2,400	Timber, veneered, vision panels	FD60S	Closers, hold-open on alarm
D-G05	Main Hall final exit, east (pair)	L00-010	1,800 (2 No. 900 leaves)	2,400	Steel, insulated	-	Panic hardware, outward opening
D-G06	Main Hall final exit, west (pair)	L00-010	1,800 (2 No. 900 leaves)	2,400	Steel, insulated	-	Panic hardware, outward opening
D-G07	Corridor C-01 to Multi-purpose Room 1	L00-050	1,000	2,100	Timber, veneered, vision panel	FD30S	Closer, intumescent strips
D-G08	Corridor C-01 to Multi-purpose Room 2	L00-050	1,000	2,100	Timber, veneered, vision panel	FD30S	Closer, intumescent strips
D-G09	Corridor C-01 to Multi-purpose Room 3	L00-050	1,000	2,100	Timber, veneered, vision panel	FD30S	Closer, intumescent strips
D-G10	Corridor C-01 to Changing Rooms	L00-050	1,000	2,100	Timber, veneered	FD30S	Closer, intumescent strips
D-G11	Corridor C-01 to Main Hall Store	L00-050	1,800 (2 No. 900 leaves)	2,100	Timber, veneered	FD30S	Closer, intumescent strips
D-G12	Corridor C-01 to stair S1	L00-050	1,000	2,100	Timber, veneered, vision panel	FD30S	Closer, intumescent strips
D-G13	Cafe to kitchen servery	L00-020	1,000	2,100	Stainless steel faced, vision panel	FD60S	Double action, kick plates
D-G14	Kitchen to service yard (external)	L00-021	1,200	2,100	Steel, insulated	-	Panic hardware, insect screen
D-G15	Kitchen to dry store	L00-022	900	2,100	Stainless steel faced	-	Kick plates
D-G16	Walk-in freezer FZ-01 door	L00-021	900	2,000	Supplied with freezer (see MEP Section 7)	-	By equipment supplier
D-G17	Walk-in chiller CH-01 door	L00-021	900	2,000	Supplied with chiller (see MEP Section 7)	-	By equipment supplier
D-G18	Changing rooms to showers	L00-040	900	2,100	Solid grade laminate	-	Privacy lock
D-G19	Stair S1 to L00 foyer	L00-001	1,000	2,100	Timber, veneered, vision panel	FD60S	Closer
D-G20	Stair S2 to L00 corridor	L00-050	1,000	2,100	Timber, veneered, vision panel	FD60S	Closer

Door	Location	Room	Width	Height	Type	Fire / smoke	Ironmongery / notes
D-101	Corridor C-02 to Library	L01-150	1,800 (2 No. 900 leaves)	2,100	Timber, veneered, vision panels	FD60S	Closers, hold-open on alarm
D-102	Corridor C-02 to Music Room	L01-150	1,000	2,100	Timber, veneered, acoustic	FD60S	Closer, acoustic seals, Rw 38
D-103	Corridor C-02 to Practice Room 1	L01-150	900	2,100	Timber, veneered, acoustic	FD60S	Closer, acoustic seals, Rw 35
D-104	Corridor C-02 to Practice Room 2	L01-150	900	2,100	Timber, veneered, acoustic	FD60S	Closer, acoustic seals, Rw 35
D-105	Corridor C-02 to Offices	L01-150	1,000	2,100	Timber, veneered, vision panel	FD60S	Closer, access control
D-106	Corridor C-02 to Youth Club	L01-150	1,000	2,100	Timber, veneered, vision panel	FD60S	Closer
D-107	Corridor C-02 to stair S1	L01-150	1,000	2,100	Timber, veneered, vision panel	FD60S	Closer
D-108	Corridor C-02 to stair S2	L01-150	1,000	2,100	Timber, veneered, vision panel	FD60S	Closer
D-109	Meeting Room 1	L01-121	900	2,100	Timber, veneered, glazed	-	Lock
D-110	Meeting Room 2	L01-122	900	2,100	Timber, veneered, glazed	-	Lock
D-R01	Plant room, from stair S1 at roof level	RF	1,200	2,100	Steel, louvred	FD60S	Closer, lock
D-R02	Plant room to roof (external)	RF	900	2,100	Steel, insulated	-	Lock, hold-open

5.3 Ironmongery

Ironmongery shall be satin stainless steel grade 316 externally and 304 internally, with lever handles to NS-EN 1906 grade 4 and closers to NS-EN 1154 adjustable for accessibility (maximum opening force 30 N). Panic hardware to NS-EN 1125. A master key suite shall be agreed with the Employer.

6. Floor, wall and ceiling finishes

Area	Floor	Skirting	Wall	Ceiling
Entrance foyer	Granite setts to entrance mat well, resin elsewhere	Resin cove	Painted plasterboard, oak panelling to reception wall	Timber slatted acoustic
Main Hall	Sprung timber sports floor, oak	Timber	Acoustic panels to 3 m, painted blockwork above	Exposed glulam, acoustic deck
Cafe	Linoleum, 2.5 mm	Timber	Painted, tiled splashbacks	Suspended acoustic tile
Kitchen	Resin, slip resistant R11, coved	Resin cove	Hygienic PVC cladding full height	Hygienic cleanable panels
Multi-purpose rooms	Linoleum, 2.5 mm	Timber	Impact resistant board, painted	Suspended acoustic tile
Changing rooms	Vinyl, slip resistant R10	Vinyl cove	Tiled full height	Moisture resistant plasterboard

Area	Floor	Skirting	Wall	Ceiling
Corridors	Linoleum, 2.5 mm	Timber	Impact resistant board to 1.2 m, painted	Suspended acoustic tile
Library	Carpet tile, heavy contract	Timber	Painted, oak shelving	Suspended acoustic tile, rooflights
Music Room	Engineered oak	Timber	Acoustic panels and diffusers	Acoustic rafts
Offices	Carpet tile, heavy contract	Timber	Painted	Suspended acoustic tile
Plant room	Sealed concrete	-	Fair faced blockwork	Exposed structure

Wall finishes in all public areas shall be impact resistant to 1.2 m above finished floor in accordance with the Employer's Requirements Section 5.8. Paint shall be low-VOC, washable, matt emulsion.

7. Fixed furniture and fittings

The Contractor shall supply and install the reception desk, cafe servery counter (excluding catering equipment, which is in the MEP Specification Section 7), library shelving (1,200 linear metres, oak veneered, adjustable), lockers, changing room benches, mirrors to Multi-purpose Room 3, and the retractable seating and stage to the Main Hall. Loose furniture is a provisional sum item.

Fixed furniture shall be designed for a 15-year service life in heavy public use. Edges shall be post-formed or solid lipped; exposed particleboard is not permitted.

8. Signage and wayfinding

A signage scheme shall be developed by the Contractor with the Employer's graphic designer, including external totem, room signs with tactile and Braille text, directional signs, statutory signs and the fire evacuation plans. Signs shall meet the universal design requirements of TEK17.

9. Handover

At completion the Contractor shall provide operation and maintenance manuals, as-built drawings in native and PDF format, commissioning records, warranties and training for the Employer's facilities staff.