Fjordview Kommune

# Fjordview Community Centre

Tender Reference FCC-2026-T01

## Document 06

# Drawing Register, Drawing Notes and Tender Programme

| Revision | Date | Status | Prepared by | Checked by |
|---|---|---|---|---|
| P01 | 2026-10-03 | Issued for Tender | Fjordview Kommune Project Team | Nordvik Rådgivning AS |

This document forms part of the tender documents for the above project. It is issued for tendering purposes only and must not be used for construction.

Note: this is a synthetic example tender pack prepared for a technical interview exercise. The project, parties and figures are fictional.

# Part A - Drawing register

The drawings listed below are issued for tender in PDF format on the procurement portal. This document reproduces the general notes and key dimensions annotated on each drawing so that they can be read with the written documents. Where a figured dimension on a drawing differs from a note in this document, the drawing governs. Drawings are not to be scaled.

| Drawing | Title | Scale | Rev | Date |
|---|---|---|---|---|
| A-100 | Site plan and external works | 1:500 | P01 | 2026-10-03 |
| A-101 | Ground floor plan L00 | 1:200 | P01 | 2026-10-03 |
| A-102 | First floor plan L01 | 1:200 | P01 | 2026-10-03 |
| A-103 | Roof plan RF | 1:200 | P01 | 2026-10-03 |
| A-201 | Sections AA and BB | 1:100 | P01 | 2026-10-03 |
| A-301 | Elevations | 1:200 | P01 | 2026-10-03 |
| A-401 | Typical wall and roof details | 1:10 | P01 | 2026-10-03 |
| S-100 | Foundation layout | 1:200 | P01 | 2026-10-03 |
| S-101 | First floor framing plan | 1:200 | P01 | 2026-10-03 |
| S-200 | Roof framing plan and glulam details | 1:200 | P01 | 2026-10-03 |
| M-100 | Ventilation schematic and plant room layout | 1:100 | P01 | 2026-10-03 |
| E-100 | Electrical single line diagram and riser | NTS | P01 | 2026-10-03 |

Level naming on the drawings follows the convention in the Instructions to Tenderers Section 1.3: L00 (Ground Floor, +0.000), L01 (First Floor, +4.200) and RF (Roof, +8.700).

# Part B - Drawing notes

## A-100 Site plan and external works

General notes: 1. Site boundary as per title deed gnr/bnr 42/118. 2. Finished floor level L00 +3.80 m NN2000. 3. Existing depot buildings shown hatched to be demolished. 4. Fjordview Primary School boundary to north; retain existing 1.8 m fence during construction.

Car park: 40 parking spaces in total, including 3 accessible spaces adjacent to the main entrance and 8 spaces with EV charging. Bays 2.5 x 5.0 m; accessible bays 3.8 x 5.0 m. Ducting shown dashed to a further 16 bays for future EV charging. Permeable block paving to all bays.

Cycle parking: 60 Sheffield stand spaces under canopy adjacent to the main entrance; 10 cargo bike spaces. Service yard: turning area for 10 m rigid vehicle; refuse store for 8 x 1,100 l containers; grease separator GS-1 in screened enclosure.

Attenuation tank AT-1 under the car park, 180 m3, outfall to Havnegata surface water sewer at 5 l/s via flow control chamber FC-1. Borehole field for ground-source heat pump: 12 boreholes under the car park at 8 m centres, shown as circles.

## A-101 Ground floor plan L00

General notes: 1. Dimensions in mm unless noted. 2. Room numbers L00-nnn refer to the Employer's Requirements room data sheets. 3. Door references D-Gnn refer to the Architectural Specification door schedule. 4. Partition types PT-nn refer to the Architectural Specification

Section 4.

Main entrance: structural opening 1,800 mm for automatic sliding doors D-G01 and D-G02, each with 2 No. 900 mm leaves. Entrance mat well 2,400 x 1,800 mm.

Main Hall L00-010: 26.0 x 20.0 m internal, column free. Stage 10.0 x 6.0 m on south wall. Retractable seating unit 300 persons on north wall, 11.0 m deep when extended. Final exits D-G05 and D-G06 at east and west, outward opening to the plaza.

Protected escape corridor C-01 (L00-050): 1,800 mm clear width, enclosed in PT-02 (EI 60). Doors D-G07 to D-G12 open from C-01 to adjacent rooms and stair S1.

Kitchen L00-021: 11.0 x 10.0 m. Walk-in freezer FZ-01 and chiller CH-01 located on the north wall, 2.4 x 3.0 m each, with remote condensing units on the roof (see A-103). Extract canopy CN-01 over the cooking line on the east wall. Service yard door D-G14 on the north wall.

Cafe L00-020: 60 covers; servery counter 6,000 mm with heated and refrigerated displays SV-01 and SV-02.

## A-102 First floor plan L01

General notes as A-101. Library L01-104: 28.0 x 15.0 m with six rooflights over. Music Room L01-110 adjacent to Library, separated by partition type PT-04. Practice rooms L01-111 and L01-112 off the Music Room lobby, partition type PT-05.

Protected escape corridor C-02 (L01-150): 1,800 mm clear width, enclosed in PT-02 (EI 60). Doors D-101 to D-108 open from C-02. Stairs S1 and S2 are protected stairs discharging to final exits at L00.

Offices L01-120 open plan with meeting rooms L01-121 and L01-122 on the west side. Youth Club L01-130 on the east side with kitchenette. Lift L1 adjacent to stair S1 serving L00, L01 and RF.

## A-103 Roof plan RF

Plant room RF-201 at roof level (finished floor +8.700), 14.0 x 8.0 m, enclosed in PT-08 blockwork with louvred door D-R01 from stair S1 and external door D-R02. The plant room houses AHU-1 to AHU-4, the heat pump, district heating substation, booster set and main switchboard MSB.

Roof plant screen 2.4 m high around the plant room and external plant. Remote condensing units for FZ-01 and CH-01 on anti-vibration mounts within the plant screen. Kitchen extract discharge 1.0 m above the screen.

Zone hatched for photovoltaic array: approximately 320 m2 on the south-facing slope of the main roof, with support structure to the structural engineer's details on S-200. Paving slab walkways on pedestals to all plant and to the PV zone. Six rooflights RL-1 to RL-6 over the Library, 1,500 x 1,500 mm.

Note: this drawing shows the extent of the PV zone only. Refer to the MEP Specification for the electrical installation.

## A-201 Sections AA and BB

Section AA through the Main Hall and foyer. Main Hall: finished floor +0.000; underside of glulam roof structure at the lowest point +5.400, giving a clear height of 5.4 m to the underside of the exposed structure; ridge +8.100. Foyer: clear height 4.2 m to the underside of the slatted ceiling.

Section BB through the kitchen, cafe and L01 Library. Kitchen L00-021: finished floor +0.000, underside of hygienic ceiling +3.000, i.e. clear height 3.0 m; service void 900 mm above. Cafe: clear height 3.2 m. L01 finished floor +4.200. Library: clear height 3.6 m to the underside of the suspended ceiling, rooflights above. Roof plant level +8.700; plant room clear height 3.5 m.

Structural zone L01 floor: 500 mm (precast hollowcore 320 mm plus 80 mm screed plus services). Service zone above suspended ceilings: minimum 600 mm.

### A-301 Elevations

North elevation (to school): fibre cement panels throughout within 5 m of the boundary, larch boarding elsewhere; no timber cladding below 1.2 m. South elevation: curtain walling to foyer and cafe, larch boarding above. Solar shading: horizontal louvres to south and west windows. All windows triple glazed, U-value 0.80 W/m2K.

### A-401 Typical wall and roof details

Detail 1 - external wall: 22 mm larch boarding, 36 mm vertical battens, breather membrane, 9 mm sheathing board, 250 mm timber frame with mineral wool, vapour control layer, 48 mm service void, 2 x 12.5 mm plasterboard. Design U-value 0.22 W/m2K.

Detail 2 - main roof: single-ply membrane, tapered PIR 240 mm average, vapour control layer, structural deck. Design U-value 0.13 W/m2K. Detail 3 - window: aluminium-clad timber frame set in the insulation zone, 30 mm thermal break at reveals.

### S-100 / S-101 / S-200 Structural drawings

Foundations: pad foundations on a bearing stratum of dense gravel at 1.5 to 2.0 m below existing ground level; allowable bearing pressure 300 kPa subject to confirmation on excavation. Ground floor slab 200 mm reinforced concrete on 300 mm compacted hardcore.

First floor: 320 mm precast hollowcore planks on steel beams, 80 mm structural screed. Design imposed loads per the Employer's Requirements Section 5.2. Roof: steel beams and purlins with metal deck; Main Hall roof: glulam beams GL30c, 1,400 x 215 mm at 4.0 m centres, span 20.0 m, exposed.

Roof plant and PV: the main roof is designed for a plant room, external plant and a PV array support structure with a total additional load of 1.5 kN/m2 over the hatched zone on A-103.

### M-100 / E-100 Services drawings

M-100: ventilation schematic for AHU-1 to AHU-4 and kitchen extract; plant room layout with maintenance access zones. Riser locations shown on A-101 and A-102.

E-100: single line diagram from the BKK Nett supply to MSB and the distribution boards listed in the MEP Specification Section 5.3. A spare 100 A way at MSB is shown for future use.

## Part C - Schedule of key figured dimensions

The table below collates the principal figured dimensions annotated on the tender drawings for ease of reference. In the event of a discrepancy the drawing governs over this table.

| Drawing | Element / room | Dimension | Value |
|---|---|---|---|
| A-100 | Site | Site area | 6,800 m2 |
| A-100 | Site | Car parking spaces (total / accessible / EV) | 40 / 3 / 8 |
| A-100 | Site | Cycle parking (standard / cargo) | 60 / 10 |
| A-100 | Site | Attenuation tank AT-1 volume | 180 m3 |
| A-100 | Site | FFL L00 | +3.80 m NN2000 |
| A-101 | L00-010 Main Hall | Internal dimensions | 26.0 x 20.0 m |
| A-101 | L00-010 Main Hall | Stage | 10.0 x 6.0 m |
| A-101 | L00-001 Foyer | Main entrance structural opening | 1,800 mm |
| A-101 | L00-021 Kitchen | Internal dimensions | 11.0 x 10.0 m |
| A-101 | L00-021 Kitchen | Walk-in freezer FZ-01 footprint | 2.4 x 3.0 m |
| A-101 | L00-021 Kitchen | Walk-in chiller CH-01 footprint | 2.4 x 3.0 m |
| A-101 | L00-050 Corridor C-01 | Clear width | 1,800 mm |
| A-102 | L01-104 Library | Internal dimensions | 28.0 x 15.0 m |
| A-102 | L01-110 Music Room | Internal dimensions | 12.5 x 8.0 m |
| A-102 | L01-150 Corridor C-02 | Clear width | 1,800 mm |
| A-102 | Lift L1 | Car internal | 1,100 x 2,100 mm |
| A-103 | RF-201 Plant room | Internal dimensions | 14.0 x 8.0 m |
| A-103 | Roof | PV zone area (hatched) | approx. 320 m2 |
| A-103 | Roof | Plant screen height | 2.4 m |
| A-201 | L00-010 Main Hall | Clear height to underside of glulam (lowest point) | 5.4 m |
| A-201 | L00-001 Foyer | Clear height | 4.2 m |
| A-201 | L00-021 Kitchen | Clear height | 3.0 m |
| A-201 | L00-020 Cafe | Clear height | 3.2 m |
| A-201 | L01-104 Library | Clear height | 3.6 m |
| A-201 | RF-201 Plant room | Clear height | 3.5 m |
| A-201 | L01 | Floor-to-floor L00 to L01 | 4,200 mm |
| A-201 | L01 | Structural zone | 500 mm |
| A-401 | External wall | Insulation thickness | 250 mm |
| A-401 | Main roof | Average PIR thickness | 240 mm |
| S-200 | Main Hall roof | Glulam beam section / spacing / span | 1,400 x 215 mm / 4.0 m / 20.0 m |
| S-200 | Main roof | Additional load allowance, plant and PV zone | 1.5 kN/m2 |

## Part D - General notes applying to all drawings

1. All dimensions are in millimetres unless stated otherwise. Levels are in metres relative to NN2000. 2. Do not scale from drawings; figured dimensions govern. 3. All dimensions shall be checked on site before fabrication. 4. Drawings shall be read in conjunction with the Employer's

Requirements and Specifications; where a higher standard is specified in the written documents, the higher standard applies. 5. Room numbers, door references and partition types are cross-referenced to Documents 03 and 04. 6. The Contractor shall report any discrepancy between drawings, or between a drawing and a written document, to the Employer's Representative before proceeding.

7. Indicative service routes shown on the architectural drawings are for coordination only; the Contractor's MEP design shall define the final routes within the service zones noted on A-201. 8. Structural member sizes shown are preliminary and shall be confirmed by the novated structural engineer in the completed design. 9. External works levels are to be coordinated with the drainage strategy and the attenuation outfall level in Havnegata.

## Part E - Programme assumptions

The tender programme assumes: a Date of Commencement of 1 March 2027 following award on 15 January 2027; that the igangsettingstillatelse is obtained within 4 weeks of application; that the ground investigation is representative and no more than 300 m3 of contaminated material is encountered; average winter weather for Vestland with 15 days of lost time allowed between November and March; and that long-lead items (glulam, lift, switchboard, AHUs) are ordered within 6 weeks of commencement.

Float: 2 weeks of terminal float is included in activity 9. No float is included in activities 3 to 7. Tenderers should state in their method statement where their own programme differs from the Employer's assumptions and how they intend to achieve the Contract Period.

## Part F - Tender programme

The Employer's indicative tender programme is summarised below. It is provided to assist Tenderers in preparing their own programme and method statement and is not a contract document. Durations are in months. Activities marked Critical are sequential on the critical path.

| No. | Activity | Duration (months) | Start | Finish | Logic |
|---|---|---|---|---|---|
| 1 | Design completion, building permit (IG) and procurement | 1.0 | 1 Mar 2027 | 1 Apr 2027 | Partly parallel with 2 |
| 2 | Mobilisation and site establishment | 0.5 | 1 Mar 2027 | 16 Mar 2027 | Critical |
| 3 | Demolition and remediation | 1.5 | 16 Mar 2027 | 1 May 2027 | Critical |
| 4 | Substructure, drainage and ground floor slab | 2.5 | 1 May 2027 | 16 Jul 2027 | Critical |
| 5 | Steel frame, precast floors and glulam roof | 3.5 | 16 Jul 2027 | 1 Nov 2027 | Critical |
| 6 | Envelope: roof, cladding, windows | 2.0 | 1 Nov 2027 | 1 Jan 2028 | Critical |
| 7 | Internal fit-out and MEP installation | 3.0 | 1 Jan 2028 | 1 Apr 2028 | Critical |
| 8 | External works and car park | 3.0 | 1 Dec 2027 | 1 Mar 2028 | Parallel with 6-7 |
| 9 | Testing, commissioning and handover | 1.5 | 1 Apr 2028 | 16 May 2028 | Critical |

Programme period: sum of critical path activities 2 to 7 and 9 = 14.5 months from the Date of Commencement (1 March 2027) to Completion (16 May 2028).

Key constraints reflected in the programme: no deliveries during school drop-off and pick-up; glulam lead time 16 weeks from order; lift lead time 20 weeks from order; BKK Nett supply connection lead time 26 weeks from application; seasonal commissioning for 12 months after Completion.

## Part G - Information documents

| Document | Status |
|---|---|
| Ground investigation report, Geoteknikk Vest AS, March 2025 | Information only |
| Environmental site assessment (hydrocarbons), June 2025 | Information only |
| Topographical survey, August 2025 | Information only |
| Planning permission FK-2025-0412 and conditions | Contract document (via Document 03) |
| Fire strategy report, Stage 3, September 2026 | Information only; to be completed by Contractor |
| Utility records: BKK Nett, Fjordview Fjernvarme, Fjordview Vann og Avløp | Information only |